



METHOD STATEMENT / INSTALLATION PROCEDURE

Edition 09.2020/v1

Sika® EmeriCrete® Topping

Installation of Separate Bonded Topping / Sikadur®-32 Hi-Mod

The following method statement represents Sika Canada Inc's recommendations for the installation of a Sika® EmeriCrete® Topping as a separate, bonded topping onto a dry concrete slab.

General	<ol style="list-style-type: none">1. Responsibility for control of conditions and adherence to the guidelines is the responsibility of the Contractor.2. Consult appropriate sections of CSA A23.1 -2019 and ACI 302 1R-15 for design and installation guidance.3. Job site conditions can influence surface drying and set time affecting the timing of topping application and finishing procedures. Experience is required to determine proper timing for required procedures.4. During cold weather open flame heaters shall not be used. Space heaters must be properly vented to avoid floor surface damage caused by carbonation or contamination.5. Hot or windy conditions may require adjustments to application procedures to offset rapid setting of topping surface. Ideally the building will have a roof and walls in place to protect from direct environment. Consider Sikafilm® to protect topping from the effects of excessive moisture loss in rapid drying conditions. <p>6. Sika® EmeriCrete® Topping may only be used by experienced professionals.</p>
Concrete Slab Preparation	<ol style="list-style-type: none">1. The concrete slab base must be sound enough to withstand the intended loads, this being determined by suitably qualified and responsible personnel.2. Minimum tensile bond strength shall be 1.5 MPa (210 psi) when tested in accordance with ASTM C1583 Standard Test Method for Tensile Strength of Concrete Surfaces.3. All surfaces are to be roughened by chipping, rotomilling, scarifying or other appropriate mechanical means to provide a roughened substrate with a minimum 3 mm (1/8 in) profile in accordance with ICRI / CSP 6.4. All fractured concrete, loose particles, detritus and grease, oil, etc., is to be removed to provide a clean, sound and stable substrate. The concrete substrate may be dry or damp, but must be free of standing water. Consult the most recent version of Sikadur®-32 Hi-Mod product data sheet for additional details and limitations.5. Non-corrosive mechanical anchors of suitable size to extend into the Sika® EmeriCrete® Topping to half its thickness are to be anchored into the concrete slab around all formed joint perimeters of the subsequent topping. Anchor positioning should be in 2 rows: one, 75 mm (3 in) from the slab perimeter at 300 mm (12 in) centres, the second, 150 mm (6 in) from the slab perimeter, again at 300 mm (12 in) centres but staggered in relation to the first row.
Priming	<ol style="list-style-type: none">1. The prepared concrete slab surface due to accept the Sika® EmeriCrete® Topping requires that Sikadur® 32 Hi-Mod be used as a bonding agent.2. Apply a bond coat of Sikadur®-32 Hi Mod at a consumption rate of not less than 1 L/m² (1 US gal/80 ft²) to achieve a uniform film build of 20 mil using a brush, roller, broom or suitable spray. For the best results, work the bonding agent well into the substrate to ensure complete coverage of all surface irregularities.3. The Sikadur®-32 Hi-Mod bond coat should receive the topping mix whilst it is still tacky and fresh. Maximum permitted open/waiting times between the application of the bonding agent and the placing of the Sika® EmeriCrete® Topping are as follows: 3.5 to 4 hours at 23 °C (73 °F), 1.5 to 2 hours at 32 °C (90 °F). If the bond coat becomes glossy and loses its tackiness, remove any surface contaminants, recoat with additional Sikadur®-32 Hi-Mod and then proceed.

Topping Installation	1. Mechanical shear mixers or a ready-mix truck are to be used to mix the constituents of the Sika® EmeriCrete® Topping. Note: We strongly recommend against manual mixing using a slow speed drill and paddle or similar equipment.
Mixing	<p>2. Water is to be used to clean and wet out the mixer, removing any material which might contaminate the topping mix; pre-wetting of the mixer is necessary to prevent reduction of the gauging water.</p> <p>3. Potable grade water is to be added to the Sika® EmeriCrete® Topping material; it should be measured to a dosage rate of approximately 8 % by weight of dry material; typically this is 2.0 to 2.25 L (0.53 to 0.60 US gal) per 25 kg (55 lb) bag of Sika® EmeriCrete® powder or 109 to 122 L (28.7 to 32.2 US gal) per 1360 kg (2998 lb) FIBC. The measurement of the water should involve the use of a suitable container which will enable accurate and repeated control of the water content and prevent over-dosing. The slump of the mixed Sika® EmeriCrete® Topping mortar is to be controlled to within Sika Canada's recommendations.</p> <p>4. The pre-measured water must be emptied into the clean, pre-wetted mixer before the powdered Sika® EmeriCrete® material is added.</p> <p>5. A sufficient number of mixers of adequate size are to be used so as not to impede systematic placing of the Sika® EmeriCrete® Topping, in accordance with installation requirements.</p> <p>6. Mixers are to be strategically placed to ensure the least amount of disturbance of the topping mix during transportation to the point of placing.</p> <p>7. The mixing time is to be approximately five (5) minutes or until the mix is totally uniform and consistent, after which the Sika® EmeriCrete® Topping mix is to be placed immediately. Note: Any and all Sika® EmeriCrete® Topping mortar showing signs of premature setting or excessive slumping is to be discarded.</p> <p>8. The Sika® EmeriCrete® Topping mix must be between 16 and 25 °C (61 and 77 °F) at the time and point of placing; consequently, care must be taken to ensure that the mixing water and the Sika® EmeriCrete® Topping powder are at a suitable temperature when mixing is undertaken.</p>
Placing	<p>1. Immediately following application of the Sikadur®-32 Hi Mod bond coat or within the permitted open/ waiting times, the correctly mixed Sika® EmeriCrete® Topping mortar should be placed by suitable means onto the prepared and primed slab, avoiding segregation of the mix.</p> <p>2. Thoroughly compact and screed the topping mortar to the specified thickness; minimum 19 mm (¾ in), maximum 37 mm (1½ in). Material consumption at 19 mm (¾ in) will be approximately 59 kg/m² (12 lb/ft²), whilst at 37 mm (1½ in), it will be approximately 111 kg/m² (23 lb/ft²).</p> <p>3. The placing and screeding operation, which could influence both adhesion and finishing of the topping, must be continuous, without delays or interruptions</p> <p>4. The Sika® EmeriCrete® Topping should be placed in panels equal to existing joint spacing in the concrete slab.</p>
Finishing	<p>1. When the applied Sika® EmeriCrete® Topping has stiffened sufficiently to support the weight of a man but limits his imprint into the topping to a maximum depth of 3 to 6 mm (⅛ to ¼ in), proceed with compacting and floating using a Kelly or equivalent compactor.</p> <p>2. Power trowelling is then to proceed as soon as the Sika® EmeriCrete® Topping begins to stiffen and lose its surface moisture sheen.</p> <p>3. As the Sika® EmeriCrete® Topping stiffens further, proceed with final trowelling to the specified finish.</p> <p>4. Wet cure the topping using Sika® UltraCure NCF™ Single-Use Wet Curing Blanket for a minimum of seven (7) days at a minimum temperature of 10 °C (50 °F). The curing is to begin as soon after final finishing as possible and when foot traffic will not damage the finish.</p>
Joints	<p>1. All construction and contraction joints are to be filled with a hard, semi-elastic joint filler such as Sika® Loadflex® or Sika® Loadflex®-524 EZ.</p> <p>2. For best results, Sika® Loadflex® sealants should be installed when the majority of concrete shrinkage has occurred and joints are static.</p> <p>3. Care must be taken to ensure that any surface contaminants on the exposed joint surface are removed prior to installing joint fillers.</p>

Notes

1. It is the responsibility of the Contractor to ensure that sufficient labour, mixing equipment, finishers etc., are available to permit the continuous preparation and placing of the Sika® EmeriCrete® Topping in accordance with the preceding method statement.
2. It is the Contractor's responsibility to possess on-site the relevant Product Data Sheet and Safety Data Sheets for all products being used.
3. The Contractor is to provide protection from rain, wind, sun and other such elements that may detrimentally affect the placing and subsequent full curing of the Sika® EmeriCrete® Topping.
4. All operations should comply with CAN/CSA A23.1-2019 Concrete Materials and Methods of Concrete Construction and CAN/CSA A23.2-2019 Methods of Test and Standard Practices for Concrete.
5. For further information, please contact Sika Canada at 1-800-933-SIKA or visit: www.sika.ca.

The Information, and in particular, the recommendations relating to the application and end-use of Sika products, are given in good faith based on Sika's current knowledge and experience of the products when properly stored, handled and applied under normal conditions, within their shelflife. In practice, the differences in materials, substrates and actual site conditions are such that no warranty in respect of merchantability or of fitness for a particular purpose, nor any liability arising out of any legal relationship whatsoever, can be inferred either from this information, or from any recommendations, or from any other advice offered. The information contained herein does not relieve the user of the products from testing them for the intended application and purpose. The proprietary rights of third parties must be observed. All orders are accepted subject to our current terms of sale and delivery. Users must always refer to the most recent issue of the local Product Data Sheet for the product concerned, copies of which will be supplied on request or may be downloaded from our website at: www.sika.ca

SIKA CANADA INC.**Head Office**

601, avenue Delmar
Pointe-Claire, Quebec
H9R 4A9

Other locations

Toronto
Edmonton
Vancouver

1-800-933-SIKA
www.sika.ca

Certified ISO 9001 (CERT-0102780)
Certified ISO 14001 (CERT-0102791)

